

Top Raised Flooring Trading LLC

Cementitious
HPL Finish
Perforated Panel

Product Description:

Perforated panel is used under air flow system, the material is steel with electrostatic spraying, the top surface is HPL finish. Airflow rate is 20%-65%. Together with the airflow sliding damper, the perforated panel performs much more efficiency on air control in date rooms, and the ventilation rate can be adjusted arbitrarily from 0-65%. Perforated panel can match with antistatic raised floor or separately use.

Panel	
Panel Size	600*600mm
Thickness	35mm
Material	Cementitious
Pattern	Small Hole
Finish	1.2mm HPL
Edge	Black PVC Trim
Color	White
Air Flow Rate	20%
Reaction to Fire	A1
Weight Per Panel/KG	7

